

## Author

### Mike Gilmore

Senior Partner of The Cabling Partnership ([www.it-cabling.com](http://www.it-cabling.com))  
Managing Director of e-Ready Building Limited  
P.O.Box MT65, Leeds, United Kingdom. LS17 8YD.  
e-mail: [mike.gilmore@e-readybuilding.com](mailto:mike.gilmore@e-readybuilding.com)  
Telephone: +44 (0) 113 232 3721

See last page for biographical details



The IT cabling infrastructure  
division of  
e-Ready Building Limited

The IT cabling consultants

e-Ready Building Limited  
Next generation IT Infrastructures

## THE CHANGING FACE OF INSTALLATION OF OPTICAL FIBRE IN DATA CENTRES

by  
**Mike Gilmore, Technical Director of the FIA  
for Networking+ (May 2008)**

By the time you read this article, IEEE may have selected the solutions for the physical implementation of 40 Gigabit and 100 Gigabit Ethernet over multimode optical fibre. It is certain that array devices (i.e. multiple VCSEL sources and detectors within a single connector) will be involved. Whether it is a 4x10Gb array to support 40 GbE or the equivalent 100 GbE array, one thing is for sure - the installation of multimode optical fibre over short distances in data centres will have changed forever.

There will be other implementations of these applications using singlemode optical fibre but these are unlikely to be economic over short distances. The maximum supportable distances using multimode optical fibre are unknown at this time but it is unlikely that they will exceed 200 metres. For longer links singlemode transmission equipment will be the only solution - but at significant cost.

This leaves the region below 200 metres (and specifically below 100 metres) retaining a cost advantage for multimode optical fibre. However, transmission distance is not the key issue. Instead, the array transmission systems place constraints on the installation of optical fibre which are only just beginning to be understood. The principal issue may be skew - the difference in time of transmission between the fastest route down the shortest optical fibre and the slowest route down the longest.

The concept of a delay skew limit is well-known to balanced cabling installers - every installed link is tested against the skew requirements. There are three important points: first, the delay skew limit is length-independent (it does not matter how long the link is); second, it applies across the four pairs of a cable and third, cable designs ensure that it is achieved.

In comparison, the concept of skew is alien to users/installers of optical fibre. Control of the differential lengths of optical fibre between two panels has never been a critical aspect of installation. It is recognised that basic techniques and yield factors for both field termination and splicing of pigtails produces different lengths - it may be that such variations become unacceptable in the future which forces us to consider the installation of pre-terminated cables with multi-fibre MPO or MTP interfaces. Many of the major systems suppliers predict this transition but most of the industry, including users, has not yet fully considered the implications of such systems.

The use of pre-terminated cables, primarily as a means to assist rapid installation, is not a new idea. Many system-suppliers have had solutions in place since the mid-1990s. However, a move towards an automatic introduction of such solutions as a day-to-day installation solution brings with it a number of challenges. Within data centres the primary design issues are cabinet cooling and overall energy efficiency. The presence of increased quantities of spare cables, as a result of inaccurate length allocation within pre-terminated cabling solutions, under floors and inside cabinets is in direct conflict with these aims.

So how are the technology demands for skew control in support of "next generation" applications going to be implemented? One approach is the significant integration of cabling, cabinets and cable management systems in order to allow accurate length determinations. Another involves the use of cabling "buffer" spaces which allow spare cables to be stored without impact on the energy efficiency of the overall data centre - but at the expense of cabinet real estate. The future appears not to be one of transmission technology but of systems design - but, have no doubt, we are all facing a change in installation approach and associated skills.

Further information will become available on the FIA web-site ([www.fia-online.co.uk](http://www.fia-online.co.uk)). Enquiries can be e-mailed to [jane@fiasec.demon.co.uk](mailto:jane@fiasec.demon.co.uk), or, alternatively, you can contact the FIA Secretariat in 01763 273039.

The Cabling Partnership  
P. O. Box MT 65, LEEDS, West Yorkshire, LS17 8YD, England  
Telephone: +44 (0) 113 232 3721

The Cabling Partnership is a division of e-Ready Building Limited  
Company Registration No. 4432595 Registered Office - Emery House, 192 Heaton Moor Road, Stockport, Cheshire, SK4 4DU.

## Biography

As the Technical and Standards Director of the UK Fibreoptic Industry Association, Mike is heavily involved in the development of training and competence standards for the fibre installation industry and sets down policy in this area. In addition he chairs the audit and arbitration committees for the FIA. His book "Fibre optic cabling; theory design and installation practice" published in 1991 remains a reference for both experts and entrants into this field.

Mike also initiated the establishment of the Telecommunications Infrastructure Advisory Board (TIA-B) along with the relevant directors of its other host organisations CMA and ECA-ITEC.

In the UK, Mike is Chairman of TCT/7, the BSI Technical Committee responsible for the three panels on telecommunication cabling. He also chairs two of these panels (TCT7/-/1 and TCT7/-/3) and is Secretary of TCT7/-/2. TCT7/-/1 and TCT7/-/2 act to assist development of European and international standards for the design and installation of telecommunications cabling respectively. TCT7/-/2 also manages the implementation of these standards in the UK, where necessary producing supporting national standards.

Mike is involved in CENELEC TC215 - as Convenor of Working Group 1 and Secretary of Working Group 2. These committees are responsible for the development of an integrated series of standards for the design and installation of telecommunications cabling in a range of premises. In 2008 he led the ETSI STF362 on energy efficiency in broadband deployment resulting in the ETSI TS 105174 series documents, allowing Mike to assist in a new TC215 activity covering data centre facilities and infrastructures (monitored in the UK by BSI TCT7/-/3).

At international level, Mike is Convenor of the Cabling Implementation Task Group (CITG) within ISO/IEC JTC1 SC25 WG3. This group is responsible for the strategic management of the international standards covering the specification, QA, installation, administration, operation, maintenance and repair of generic cabling. This work supports all the cabling design standards produced by ISO/IEC JTC1 SC25 WG3 including ISO/IEC 11801, ISO/IEC 15018, ISO/IEC 24764 and ISO/IEC 24702 for industrial premises produced by ISO/IEC JTC1 SC25 WG3 IPTG (also convened by Mike Gilmore).

Mike is a regular speaker at seminars and conferences in all five continents. He has provided the keynote address and opening presentation in many conferences in the UK, Germany and the Netherlands. His seminars, providing regular updates on the progression of cabling standards are particularly well attended and are operating in the UK and continental Europe.



The Cabling Partnership  
P. O. Box MT 65, LEEDS, West Yorkshire, LS17 8YD, England  
Telephone: +44 (0) 113 232 3721

The Cabling Partnership is a division of e-Ready Building Limited  
Company Registration No. 4432595 Registered Office - Emery House, 192 Heaton Moor Road, Stockport, Cheshire, SK4 4DU.